

**NOTICE**

**INVITING TENDERS: REPAIR / MODIFICATION OF BUILDINGS**

1. Sealed Tenders are invited by 21 Nov 2023 repair / modification of buildings of Army College of Nursing, Jalandhar Cantt.
2. The details of repairs / modification required are attached as Appendix.
3. Interested parties may visit the site/ area on any working day between 8:30 AM to 3:30 PM.

Registrar

**DETAILS OF MODIFICATIONS / REPAIR WORKS :**  
**ACN JALANDHAR**

<b>Ser No</b>	<b>Name of work/ Description of store</b>	<b>A/U</b>	<b>Qty</b>
1	Dismantling/demolition of existing platform Granite top incl brick work complete removal of debris/excavated materials from site and fixing of kota stone slab of affected area matching with existing kota stone flooring complete all as directed (size of existing platform (5.50m x 1.80m)	Nos	3.00
2	M&L for brick work, laying of granite slab of size <b>12.00m x 0.60m</b> over concrete base, with aluminum frame and bakelite sheet 6mm thick shutter shelf height 600 mm incl locking arrangement, chromium plated/stainless steel handles, hinges etc, incl 01 x stainless steel sink 1 mm thick for laboratory of overall size 495mmx420mm, bowl size 410mmx330mm x160mm, stainless coupling, waste pipe, sink taps, CP soap dish, stainless steel grating suitable water supply and plumbing work complete all as directed.	Job	2.00
3	Removal of bakelite sheet with aluminum frame partition cubical and same shall be refixing at site as directed.	Job	1.00
4	Addition/alteration of Café Complex shops into NCC/NSS/ YRC Office - 03 Nos		
	(i) Demolition of existing brick wall for fixing doors.	Cum	2.25
	(ii) Fabrication and fixing of powder coated aluminum door shutter of section 2 mm thick with aluminum frame (Chaukhat) section 3 mm thick partially glazed partially fixed with 6mm thick bakelite sheet and glazed portion shall be fixed with 10 mm thick toughen glass incl locking arrangement six level stainless steel lock, neoprene packing complete fittings and fixtures as approved by the consignee shall be provided. <b>Make of Aluminum - Jindal/TATA/HINDALICO</b>	Nos	3.00
	(iii) Dismantling of existing MS shutter door	Nos	3.00

	(iv) Brick work for MS shutter portion in cement mortar 1:6 ( Size of the MS shutter 3.00m x 2.70m), rendering in CM 1:6 and painting with OBD matching with the existing colour complete all as directed by the consignee.	Job	3.00
	(iv) Supply and fixing of powder coated Aluminum window side hung of size 1.22m x 1.22 m glazed and gauged with Aluminum guard bars, 5.5 mm thick plain glass, stainless steel wire mesh shall also be provided with complete fittings and fixture complete all as directed. <b>Make of Aluminum - Jindal/TATA/HINDALICO</b>	Nos	3.00
	(v) Supply and fixing of 0.60 mm thick PPGI sheet sun shed of 450 mm wide and 300 mm wider than opening shall be provided where door/window are open to sky shall be fixed over ISA 25x25x3 mm frame as approved by the consignee	Nos	3.00
	Complete internal periodical, electric wiring with copper conductor, modular type switch socket, power socket shall be provided in each room	Nos	3.00
5	Removal of existing sinks and fixing of granite slab at affected area matching with the existing granite slab flooring complete all as directed.	Nos	8.00
6	Drawer made of 2 mm thick aluminum frame with bakalite 4 mm thick sheet shutter at Nut Lab including complete fittings and fixture including handle, hinges and suitable locking arrangement complete all as directed. Height of the drawer shall be 600 mm high <b>Make of Aluminum - Jindal/TATA/HINDALICO</b>	Nos	1.00